



10888 Hickman Rd, Ste 3B
Clive, IA 50325
(515) 334-3340 Office
(515) 334-3346 Fax

16742 Verona Hills Dr, Clive, Iowa
Lot 9, Verona Hills South Plat 1

4 bedroom, 2 ½ bath
2307 Square Feet

Structural:

- 9 foot foundation with full basement and 2 egress window wells
- Interior and exterior of foundation tiled with Form-a-Drain draining to sump pump, tied to City storm sewer
- Tuff n' Dry spray on waterproofing (10 year warranty)
- 2" x 4" and 7/ 16" OSB framed construction with 11 7/8" LP I-Joists floors and custom R & D roof truss system (supplied by Munn Lumber)
- Fully sheathed in Tyvek brand housewrap
- 4000 psi concrete basement floor, garage floor, driveways, and sidewalks
- Blown in Cellulose insulation in walls (16 ½ R-Value) and attic (40 R-Value). All joints and small spaces sealed with caulk and foam
- Blanket insulated foundation walls (11 R-Value)
- 3rd party energy efficiency testing and consultation throughout the building process. Blower door testing and Energy Star certification by The Element Group.

Mechanical:

- Ruud high efficiency furnace and air conditioner with humidifier with programmable thermostat.
- 50 gallon Rheem power vent hot water heater
- Central Vac pre-plumbed
- Security pre-wired
- Cable and phone in all bedrooms, phone in kitchen, cable in family room.
- Cat 5 phone wiring can be used for data/ Ethernet as well
- Basement bath stubbed for ¾ bath

Exterior Finishes and Features:

- James Hardie HardiPlank fiber cement board and MiraTEC trim siding exterior with Centurion cultured stone
- Low maintenance Anderson 100 series single hung windows and sliders with Low E glass and screens. Matching fiberglass entry door.
- 30 year architectural asphalt shingles with Ice Guard where necessary



10888 Hickman Rd, Ste 3B
Clive, IA 50325
(515) 334-3340 Office
(515) 334-3346 Fax

- 3 car garage with Wayne Dalton doors (9 R-value) 2 Chamberlain Lift-Master openers & 1 keypad
- Soffit can lighting
- Sherman Williams Super Paint flat, 1 body, 1 trim, and 1 accent color (front)
- 14' x 14' treated wood deck with stairs and executive railing design package
- Full sod
- Full irrigation system installed

Interior Finishes and Features:

- Large painted craftsman-style trim package. Fireplace mantle, tub front, stair parts, etc stained to match cabinetry
- Custom stained cubby/ locker set
- Metal spindles in staircase railing
- Paramount Legacy maple cabinets
- 3 cm granite in kitchen, master, and hall baths
- Full premium tile backsplash in kitchen and fireplace surround
- GE stainless steel kitchen appliance package (dishwasher, range, microwave)
- Tile in baths, laundry, mud room
- Hardwood floors or tile in entry and kitchen
- Shaw nylon frieze carpet 3 tone (one ceiling, one wall, one trim) high quality paint. Pittsburg Paint Infinium washable flat walls and Manor Hall semi-gloss trim
- Extensive can lighting and executive fixtures
- Jet tub in master bath
- Brushed nickel Danze Melrose line bath fixtures
- 5 foot tiled shower with shower door
- Brushed nickel lever style door hardware and towel bar package
- Wire shelving package in closets and pantry
- Full mirror package

Additional Information:

- One year Builder Warranty based on the National Association of Homebuilders Residential Construction Performance Guidelines (version 3)
- Many additional warranties provided thru individual manufacturers and installers
- Any additional upgrades or changes shall be agreed to in writing & shall be added to the purchase price.
- Materials or specs may change through the building process and this list is meant to be an estimate of finishes and materials.